

**Alabama Department of Transportation  
Proposal Item Summary**

**064. STPAA-0248(501) & 99-407-162-248-501**

**COFFEE COUNTY**

Contract Time: 90 Working Days

DBE Goal Percent: 10.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-248 (Glover Avenue) from the junction of SR-27 to east of the junction of Freedom Drive to include the Drainage Structure Improvements east of the junction of SR-27 (East Lee Street) in Enterprise. Length 3.331mi.

The Bracket Estimate on this project is from \$1,502,042 to \$1,835,829.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$18.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D000	76	LF	Removing Pipe
206D001	27	LF	Removing Guardrail
206D002	418	LF	Removing Curb
206E008	1	Each	Removing Guardrail End Anchor (All Type)
210A000	1,100	CUYD	Unclassified Excavation
210D021	1,400	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	835	CUYD	Structure Excavation
214B001	1,250	CUYD	Foundation Backfill, Commercial
230A000	1	RBST	Roadbed Processing
301A025	225	SQYD	Crushed Aggregate Base Course, Type B, Road Mixed, 6" Compacted Thickness
401A000	225	SQYD	Bituminous Treatment A
405A000	9,797	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	97,965	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	8,101	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	275	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	18	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	22	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
502A000	23,000	LB	Steel Reinforcement
524A011	142	CUYD	Culvert Concrete (Cast In Place)
533A098	266	LF	18" Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
602A000	8	Each	Right Of Way Markers
606A000	500	LF	6" Underdrain Pipe
610C001	280	Ton	Loose Riprap, Class 2
610D003	100	SQYD	Filter Blanket, Geotextile
614A000	6	CUYD	Slope Paving
621C015	4	Each	Inlets, Type S1 Or S3 (1 Wing)
621D015	3	Each	Inlet Units, Type S1 Or S3
623C000	367	LF	Combination Curb & Gutter, Type C
650A000	15	CUYD	Topsoil

Item No.	Quantity	Units	Description
654A001	90	SQYD	Solid Sodding (Bermuda)
665J002	150	LF	Silt Fence
665O001	150	LF	Silt Fence Removal
665P005	4	Each	Inlet Protection, Stage 3 Or 4
665Q002	300	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 79,500.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	6	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,485	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	16	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	7,253	SQFT	Traffic Control Markings, Class 2, Type A
703B002	561	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,767	SQFT	Temporary Traffic Control Markings
703E001	579	SQFT	Temporary Traffic Control Legends
703H000	3	SQFT	Specialty Traffic Control Markings
705A030	914	Each	Pavement Markers, Class A-H, Type 2-C
705A032	270	Each	Pavement Markers, Class A-H, Type 1-B
705A037	754	Each	Pavement Markers, Class A-H, Type 2-D
705A038	546	Each	Pavement Markers, Class A-H, Type 2-E
726A000	100	LF	Portable Concrete Safety Barriers, Type 6
730H001	10,250	LF	Loop Wire
740B000	1,147	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740F001	12	Each	Barricades, Type II
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2