

**LEBANON COUNTY – SR 1011(018) #90998**

**PROPOSAL:\$17.28 PLANS:\$7.04 12X18:\$8.64 24X36:\$124.80 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30**

This project consists of the replacement of an existing deteriorated two-span, rigid frame culvert with a precast concrete arch on cast-in-place spread footings. Work also includes minor roadway approach work and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 1011, SECTION 018, in LEBANON COUNTY, NORTH LEBANON TOWNSHIP, from Segment 0050 Offset 2332 to Segment 0050 Offset 2712, for an overall project length of 275.00 linear feet (0.052 mile).

---

**BERKS COUNTY – SR 737(03B) #92028**

**PROPOSAL:\$20.64 PLANS:\$16.28 12X18:\$19.98 24X36:\$288.60 X-SEC:\$3.30 12X18:\$4.05 24X36:\$58.50 Ex**

**St:\$0.22 12x18:\$0.27 24x36:\$3.90** The project is to replace a 10 foot single span concrete slab bridge with a 10 by 4 foot precast concrete box culvert on new alignment, construct new intersection with SR 1021, remove existing structure and restore stream through the area. Total length of realigned roadway will be 1175 feet and will include guiderail, bituminous curb, signing and pavement marking and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0737, SECTION 03B, in BERKS COUNTY, MAXATAWNY TOWNSHIP from Segment 0030 Offset 0501 to Segment 0020 Offset 0126 and STATE ROUTE 1021, SECTION 01R from Segment 0230 Offset 0000 to Segment 0230 Offset 0357, for an overall project length of 1482.19 linear feet (0.281 mile).

---

**BERKS COUNTY – SR 183(07S) #57840**

**PROPOSAL:\$27.24 PLANS:\$34.98 12X18:\$42.93 24X36:\$620.10 X-SEC:\$24.20 12X18:\$29.70 24X36:\$429.00**

The project is a roadway re-alignment of an auxiliary right turn lane and traffic signal at the intersection of SR 0183 (Bernville Road) and SR 4016 (New Schaefferstown Road), located in Jefferson Township. Construction consists of roadway re-alignment, replacement of existing structure with a single span composite spread box beam bridge, new traffic signal, highway lighting, guide rail, signing and pavement markings, and other miscellaneous items, all as indicated on the approved drawings included in the bid package for STATE ROUTE 0183, SECTION 07S, in BERKS COUNTY, JEFFERSON TOWNSHIP, from approximately 2.1 miles east of Bernville at Segment 0290 Offset 1878 to approximately 1200 feet past the intersection with SR 4016 at Segment 0300 Offset 0875, and STATE ROUTE 4016, SECTION 07S, from the intersection with SR 0183 at Segment 0110 OFFSET 0449 to approximately 1000' north of the intersection with SR 0183 at Segment 0100 Offset 1699, for an overall project length of 2,540.75 linear feet (0.481 miles).

---

**ADAMS COUNTY – SR 1007(016) #78638**

**PROPOSAL:\$19.20 PLANS:\$17.60 12X18:\$21.60 24X36:\$312.00 X-SEC:\$3.08 12X18:\$3.78 24X36:\$54.60 Ex**

**St:\$1.32 12x18:\$1.62 24x36:\$23.40** This project consists of one bridge superstructure replacement with a two-span prestressed concrete spread box beam superstructure and one bridge replacement with a precast concrete box culvert and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for: STATE ROUTE 1007, SECTION 016, in ADAMS COUNTY, LATIMORE & READING TOWNSHIPS, from Segment 0070 Offset 3971 to Segment 0080 Offset 1426, and for STATE ROUTE 3010, SECTION 011 in ADAMS COUNTY, HAMILTONBAN TOWNSHIP, from Segment 0020 Offset 0538 to Segment 0020 Offset 1128.

---

**MONTGOMERY COUNTY – SR 3037(BRS) #107697**

**PROPOSAL:\$22.56 PLANS:\$25.52 12X18:\$31.32 24X36:\$452.40 X-SEC:\$5.06 12X18:\$6.21 24X36:\$89.70**

This project will stabilize the Balligomingo Road and Brandywine Creek Road to address the slope failure now and for the future, this project involves slope stabilization, drainage improvements, pavement repair and replacement work. Construction activities involves the installation of a soldier pile retaining wall along the toe of the failed slope areas to stabilize the embankment slope and roadway rock protection and other miscellaneous construction, as indicated on the approved drawings included in the bid package for Balligomingo Road (SR 3037) SEC BRS, in Montgomery County, West Conshocken Borough from approximately at segment 0012 offset 3873 to approximately at segment 0022 offset 1600. For Brandywine Creek Road (SR 3095) SEC BCR, in Chester County from approximately at segment 0014 offset 0836 to approximately at segment 0014 offset 2091.

---