

Addendum Date: February 11, 2020

CITY OF PENSACOLA, FLORIDA
ADDENDUM #2

DEVILLERS STREET REVITALIZATION

PHASE 1: FROM MAIN STREET TO GARDEN STREET

The following items take precedence over the documents for the above named items. All other terms and conditions shall remain the same.

A SIGNED COPY OF THIS ADDENDUM MUST BE RETURNED WITH YOUR SUBMITTAL

Company: _____ Date: _____

Authorized
Representative: _____ Title: _____
Printed Name

Signature: _____

PLEASE RETURN A COPY OF THIS ADDENDUM AS ACKNOWLEDGEMENT

In order to clear up some confusion and clearly labeled all storm structures in the project the bid tab and schedule of values have been changed in their entirety. The new/corrected bid tab and schedule of values are attached to this document.

Changes to Bid Tab and Schedule of Values

- The previous bid tab and schedule of values have been updated to note that the contract will not furnish, but only install the street name embeds.

**FINAL DEVILLIERS STREET REVITALIZATION PROJECT
PHASE I BID TABULATION ADDENUM # 1**

No.	ITEM	QTY	UNIT	UNIT COST	TOTAL
1.0 Roadway					
1	MOBILIZATION (INCLUDES PERMITTING)	1	LS		
2	TRAFFIC CONTROL AND DETOUR SIGNAGE (FURNISH, INSTALL & MAINTAIN)	1	LS		
3	CLEARING AND GRUBBING\SAW CUTTING\MISCELLANEOUS ASPHALT REMOVAL	1	LS		
4	EROSION CONTROL (FURNISH, INSTALL & MAINTAIN)	1	LS		
5	EARTHWORK (MINOR REGRADING/SHAPING/FILL/EXCAVATION)	1	LS		
6	REMOVAL AND DISPOSAL OF CONCRETE	1	LS		
7	SIDEWALK CONCRETE (4" THICK WITH TURNDOWN PAVER EDGE) (FURNISH & INSTALL) (3000 PSI)	2251	SY		
8	SIDEWALK CONCRETE (6" THICK FOR DRIVEWAYS) (FURNISH & INSTALL) (3000 PSI)	671	SY		
9	12" CONCRETE RIBBON CURB (6" THICK) (FURNISH & INSTALL) (3000 PSI)	202	LF		
10	FDOT TYPE D CURB (FURNISH & INSTALL)(3000 PSI)	14	LF		
11	DETECTABLE WARNINGS PAVERS (SEGMENTAL CAST IRON TRUNCATED DOME) (FURNISH & INSTALL)	349	SF		
12	60 MM CONCRETE PAVER SIDEWALK EDGE SOLDIER COURSE (2 SIDES & DETAILS) (FURNISH & INSTALL)	6490	LF		
13	6" SOLID WHITE THERMOPLASTIC (FURNISH & INSTALL)	526	LF		
14	6" DOUBLE YELLOW INCLUDING RPM'S (FURNISH & INSTALL)	200	LF		
15	24" SOLID WHITE THERMOPLASTIC CROSSWALK (FURNISH & INSTALL)	628	LF		
16	24" WHITE STOP BAR THERMOPLASTIC (FURNISH & INSTALL)	111	LF		
17	12" CROSSWALK WHITE THERMOPLASTIC (FURNISH & INSTALL)	548	LF		
18	8" WHITE THERMOPLASTIC (FURNISH & INSTALL)	376	LF		
19	CONFLICTING PAVEMENT MARKING REMOVAL (HYDROBLASTING)	1	LS		
20	SIGN RELOCATION	4	EA		
21	COMPASS ROSE EMBOSSING TEMPLATE WITH 10% SURPLUS (FURNISH & INSTALL)	39	EA		
22	INSTALL CAST IRON STREET NAME EMBEDDED IN SIDEWALK (CITY WILL FURNISH)	18	EA		
TOTAL: ROADWAY					

2.0 LANDSCAPE					
1	STANDARD NATCHEZ CRAPE MYRTLE (FURNISH & INSTALL)	80	EA		
2	SUNSHINE LIGUSTRUM (FURNISH & INSTALL)	175	EA		
3	ASIAN JASMINE (FURNISH & INSTALL)	2581	EA		
4	TREE REMOVAL	2	EA		
5	TREE PRUNING/VINE REMOVAL (UP TO 10 FEET ABOVE SIDEWALK & ALONG R/W)	1	LS		
6	MULCH - 3" DEPTH PINE STRAW (FURNISH & INSTALL)	1322	SY		
7	MULCH - 1.5" DEPTH PINE STRAW (FURNISH & INSTALL)	1322	SY		
8	1-YEAR MAINTENANCE	1	LS		
TOTAL: LANDSCAPE					

3.0 IRRIGATION					
1	IRRIGATION COMPLETE	1	LS		
TOTAL: IRRIGATION					

4.0 LIGHTING					
1	LIGHT POLES & CONCRETE BASES (FURNISH CONCRETE BASE & INSTALL)(LIGHT POLE TO BE PURCHASED BY CITY)	39	EA		
2	NEW PANEL BOARD WITH BREAKERS FURNISH & INSTALL)	1	EA		
3	NEW SURGE SUPPRESSOR (FURNISH & INSTALL)	1	EA		
4	NEW CONTACTOR (FURNISH & INSTALL)	2	EA		
5	PANEL BOARD ENCLOSURE (FURNISH & INSTALL)	1	EA		
6	DIRECTIONAL BORE MOBILIZATION	1	EA		
7	DIRECTIONAL BORE (INSTALL)	500	LF		
8	TRENCH (INSTALL)	3400	LF		
9	#6 WIRE (FURNISH & INSTALL)	273	CLF		
10	2" PVC (FURNISH & INSTALL)	3900	LF		
EXHIBIT SUB TOTAL					

Grand Total

ALTERNATE # 1					
1	DETECTABLE WARNINGS PLASTIC (FURNISH & INSTALL)	349	SF		
2	DETECTABLE WARNINGS PAVERS (SEGMENTAL CAST IRON TRUNCATED DOME) (DEDUCT)	349	SF		
TOTAL ALTERNATE # 1					

ALTERNATE # 2					
1	PERFORMANCE TURF (FURNISH & INSTALL)	1147	SY		
2	PREPARED SOIL LAYER, FINISH SOIL, 6" (FURNISH & INSTALL)	1147	SY		
3	ASIAN JASMINE (DEDUCT)	2581	EA		
4	IRRIGATION COMPLETE (PARTIAL DEDUCT - ASIAN JASMINE AREA)	1	LS		
TOTAL ALTERNATE # 2					

ALTERNATE # 3					
1	DETECTABLE WARNINGS TRUNCATED DOME BRICK PAVERS (FURNISH & INSTALL)	349	SF		
2	DETECTABLE WARNINGS PAVERS (SEGMENTAL CAST IRON TRUNCATED DOME) (DEDUCT)	349	SF		
TOTAL ALTERNATE # 3					

