

DATE: February 28, 2020

TO: All Holders of Plans for Project No. MTCE R300-255

SUBJECT: Revision No. 1 (to be acknowledged in all bid proposals)

Reason(s) for Revision

Plan or Spec Correction       Commencement or completion time change  
 Biddable quantity changes       Add or delete specs  
 Add or delete plan sheet       New Davis Bacon wage rates  
 Funding availability       Other (explain) Change in the number of working days.

Bid Proposal:

Revised Schedule. Prospective bidders must submit their bids on the revised schedule, see the schedule amendment posted on the CDOT web site and Bid Express.

Project Special Provisions:

Page 1a: Revised Index  
Page 4a: Commencement and Completion of Work  
Page 9a: Revision of Section 108, Working Time Limitations

Standard Special Provisions:

N/A

Plan Sheets:

Sheet 1a: Title Sheet and Index  
Sheet 7a: Summary of Approximate Quantities

Please substitute the enclosed revisions in your copy of plan documents and destroy those sheets superseded by this transmittal.

The Department has delayed the bid opening 1 week for this project. Bids will be opened on Thursday March 12, 2020. A new EBS file has been posted on the web to correspond to the revised bid opening date. Bidders using EBS must use the new file.

This revision is authorized by Andi Staley, PE II.

cc: FHWA, Colo F/A Division Operations Eng. (If FHWA Oversight)  
J. Stiller, Bid Plans  
T. Benton, Engineering Contracts  
J. Arcilla, Business Programs  
R. Simmons, Engineering Contracts  
S. Bokros, Cost Estimating  
Central Files  
Project Manager  
Resident Engineer

COLORADO  
DEPARTMENT OF TRANSPORTATION  
SPECIAL PROVISIONS  
R3 FY 20 REGION WIDE ROUNDABOUT STRIPING  
MESA, GARFIELD, EAGLE, PITKIN, AND SUMMIT COUNTIES

The 2019 Standard Specifications for Road and Bridge Construction controls construction of this project. The following special provisions supplement or modify the Standard Specifications and take precedence over the Standard Specifications and plans.

PROJECT SPECIAL PROVISIONS

		<u>Page</u>
Index Pages	(February 7, 2020)	1 - 2
Notice to Bidders	(February 7, 2020)	3
Commencement and Completion of Work	(February 7, 2020)	4a
Contract Goal (Combined)	(February 7, 2020)	5
OJT Contract Goal	(February 7, 2020)	6
Revision of Section 102 - Project Plans and Other Data	(February 7, 2020)	7
Revision of Section 105 – Cooperation between Contractors	(February 7, 2020)	8
Revision of Section 108 – Working Time Limitations	(February 7, 2020)	9a-10
Revision of Section 108 – Liquidated Incentive	(February 7, 2020)	11
Revision of Section 109 – Partial Payments	(February 7, 2020)	12
Revision of Section 614 – Tubular Steel Sign Support	(February 7, 2020)	13
Revision of Section 630 – Portable Message Sign Panel	(February 7, 2020)	14-15
Revision of Section 630 – Mobile Attenuator	(February 7, 2020)	16-17
Force Account Items	(February 7, 2020)	18
Traffic Control Plan – General	(February 7, 2020)	19-20
Utilities	(February 7, 2020)	21

**[YELLOW PLAN SHEETS FOLLOW SPECIAL PROVISIONS]**

COMMENCEMENT AND COMPLETION OF WORK  
(WORKING OR CALENDAR DATE)

The Contractor shall commence work under the Contract on or before the 15<sup>th</sup> day following Contract execution or the 30th day following the date of award, whichever comes later, unless such time for beginning the work is changed by the Chief Engineer in the "Notice to Proceed." The Contractor shall complete all work within 150 working days in accordance with the "Notice to Proceed."

Subsection 108.05 shall include the following:

The Contractor shall complete the following discrete portions of the work (milestones) by the dates specified. A disincentive will be assessed for failure to complete the work for each milestone by the specified completion date.

Milestone No. 1 Complete Work Zones 1, 2, 3, 4, and 5.

Work Zone 1 – 50A with Frontage Roads – MP 34.62 to 165.601

Work Zone 2 – 50D – MP 0.0 to 1.539

Work Zone 3 – 550B – MP 117.514 to 130.209

Work Zone 4 – 70E – MP 0.0 to 0.222

Work Zone 5 – 91A from MP 0.0 to 22.605

Completion Date: June 30, 2020

Description: Complete all of the work shown on the spreadsheets for work zones 1 through 5.

Incentive and Disincentive: As per the liquidated incentive project special Section 108.

Section 108 of the Standard Specifications is hereby revised for this project as follows:

Subsection 108.03 shall include the following:

The Contractor's progress schedule may be a Bar Chart Schedule. Job Progress narrative report and schedule shall be submitted by-weekly and with all updates. It shall detail the description of job progress, problem areas, current and anticipated delaying factors and their anticipated effects, impacts to job milestones or project completion, any corrective action proposed or taken, and any minor revisions to the Schedule.

Salient features to be shown on the Contractor's Progress Schedule are:

- (1) Mobilization time
- (2) Notice to locators
- (3) Weekly working time schedule
- (4) Placement of Material Orders
- (5) Production Rates for each activity
- (6) Post base installation by Work Zone and mile post
- (7) Sign replacement by Work Zone and mile post
- (8) Sign Pickup by Work Zone

### **REVISION OF SECTION 108 WORKING TIME LIMITATIONS**

Section 108 of the Standard Specifications is hereby revised for this project as follows:

Subsection 108.05 Limitation of Operations shall include the following:  
The following working time limitations shall be in effect:

No more than 12 hours in a 24 hour period shall be available for a work day. "No Work" timeframes shall be as designated by the Project Engineer. No work shall take place on state holidays or during major events as directed. "No Work" shall be defined such that all equipment shall be removed from the traveled way.

The Contractor shall limit work to a defined Work Area. A Work Area is defined as one detailed Method of Handling Traffic. Contractor can work in up to two work zones at a time. Each work zone shall be completely separate, requiring a separate TCM, supervisor, crew and equipment. These two work zones shall work independent of each other, shall have a separate CDOT inspector and shall be agreed upon by the Project Engineer. A TCM day can be charged for each complete work zone. Contractor may perform work in multiple Work Sites in one Work Zone as approved by the Project Engineer. Work Sites shall be less than or equal to a maximum of two miles for Work Zones within Populated areas. Work sites shall be less than or equal to five miles for Work Zones within Rural areas as defined by the Project Engineer. The distance between sites shall not exceed 20 miles.

For lane closure and working time limitation the Region 3 Lane Closure Strategy, 3<sup>rd</sup> Edition shall be in effect and can be found at:

<http://www.coloradodot.info/library/traffic/traffic-manuals-guidelines/lane-close-work-zone-safety/lane-closure-strategies>

Subsection 108.08 Determination and Extension of Contract Time:

During holidays that result in a three-day weekend, the contractor shall cease work on the project by 12:00

P.M. on the day preceding the holiday weekend, and shall resume work after 7:00 A.M. on the day following the holiday weekend as approved.

Subsection 108.09 Failure to Complete Work on time shall include the following:

New sign fabrication for this project will be completed by the CDOT Sign Shop located at the KOA Complex, 1386 Tower Road, Aurora, CO 80011. Initial coordination shall be made thru the Project Engineer, additional coordination for pick-up of all signs from the CDOT Sign Shop shall be accomplished during business hours with the Sign Shop Supervisor, Mr. Bernard Cole, who can be reached at 303-365-7322 or 720-413-1073. Business hours for the CDOT Sign Shop are Monday through Friday, 7:00 a.m. to 3:30 p.m.

Sign fabrication shall be completed for each corridor in its entirety before beginning fabrication of signs on a subsequent corridor. A sign pickup request schedule per work zone shall be provided by the Contractor as part of the Progress Schedule submittal at the Pre-Construction Conference. The maximum time required for the Contractor to pick up signs for each work zone shall be 7 days after notice to proceed for Work Zone 1 and 5 working days for all other Work Zones.