

CONTRACTOR WILL REVIEW AND PRICE EACH PHASE SEPARATELY AND PROVIDE A TOTAL CONSTRUCTION COST FOR ALL PHASES BELOW.

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE A - BID FORM PROPOSAL

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE A - Section A: Roadway / Trail					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
140-1000	1	LS	MOBILIZATION		
150-1000	1	LS	TRAFFIC CONTROL		
205-0001	3.7	CY	REMOVE UNCLASS MATERIAL, HAUL TO HAZARDOUS WASTE LANDFILL		
210-0100	1	LS	GRADING COMPLETE		
402-1802	1	LS	ROADWAY PAVEMENT CUT & PATCH FOR NEW STORM SEWER (PER GDOT STD. 1401) (FIELD ST. STA 10+20 TO 11+25)		
400-3101	225	TN	ASPH CONC 12.5mm SUPERPAVE GP 2 PNLV, INCL BITUM MTL, GILSONITE MODIFIER & H LIME (E WASHINGTON)		
432-0200	2300	SY	MILL EXISTING ASPHALT SURFACE, MILL DEPTH VARIES (E WASHINGTON)		
441-0018	75	SY	CONC DRIVEWAY APRON, 8 IN (PER GDOT STD. A2)		
444-1000	1,900	LF	SAWED JOINTS IN EXISTING PAVEMENTS -PCC		
441-5002	536	LF	CONCRETE HEADER CURB, 6 IN, TP 2		
441-5004	15	LF	CONCRETE HEADER CURB, 10 IN, TP 4		
441-6022	770	LF	CONC CURB & GUTTER, 6 IN X 24 IN, TP2		
441-0105	2,432	SY	CONCRETE TRAIL & SIDEWALK, CL 3000 PSI, 5 IN, 10-12 FT (INCL ADA RAMPS)		
500-3800	4	CY	CLASS A CONCRETE STAIRS (INCL REINF), PER DETAILS		
500-3800	29	CY	HEAVY DUTY CONCRETE TRAIL, 8 IN (INCL CONC APRON)		
515-1001	120	LF	ALUM ORNAMENTAL RAILING, 4 HT, BLACK		
515-1002	35	LF	HANDRAIL @ STAIR LOCATIONS, 1-1/2" I.D. PIPE, POWDERCOATED BLACK		
611-5029	45	LF	RECONSTRUCT & MOVE CHAIN LINK DOG PEN (STA 11+70), PER PLANS		
611-5360	1	EA	RESET EXISTING HIGHWAY SIGN, 'SPEED LIMIT' (STA 4+34)		
611-5550	1	EA	RESET EXISTING SIGN, 'NEWNAN LOFTS LEASING OFFICE' (STA: 11+35)		
611-5551	1	EA	RESET EXISTING SIGNS, 'NO PARKING FIRE LANE' (STA: 9+50 TO 11+00)		
611-5552	1	EA	RESET EXISTING MAILBOX (E WASHINGTON ST, STA: 7+00)		
643-8300	415	LF	ALUM PRIVACY FENCE, 6' HT, BLACK, PER DETAILS		
643-1452	240	LF	VINYL-COATED CHANLINK FENCE, 6' HT, BLACK		
643-8200	765	LF	BARRIER TREE FENCE (ORANGE), 4' HT		
636-1041	139	SF	LINC TRAIL SIGN MATL 0.125 ALUM, DIRECT PRINT, PER DETAILS		
681-3740	15	EA	REGULATORY SIGN SQUARE ALUMINUM POST, PER DETAILS		
636-1033	66	SF	MUTCD HIGHWAY SIGNS		
636-3010	112	LF	MUTCD HIGHWAY SQUARE POST, 14 FT, BREAKAWAY		
222-1002	128	SY	#57 STONE (CLEAN), 6 IN, (ROOT BRIDGING AREAS)		
603-7000	128	SY	PLASTIC FILTER FABRIC (ROOT BRIDGING AREAS)		
652-5302	116	LF	TRAIL CROSSWALK STRIPE, 12 IN, GREEN CASTEK COLOR SAFE ANTI-SKID, PER DETAILS.		
652-6403	1,900	LF	PAINT SKIP TRAF STRIPE, 4 IN, NEWNAN LINC GREEN (TRAIL CL)		
653-0100	1	EA	THERMOPLASTIC RR CROSSING MARKING, SOLID WHITE (PER GDOT STD 9024A)		
653-1804	141	LF	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN WHITE, 8' WIDE (GDOT CROSSWALKS)		
653-1804	700	LF	THERMOPLASTIC SOLID TRAFFIC STRIPE, 8IN, WHITE (EDGE STRIPING)		
653-1502	1200	LF	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5IN, YELLOW		
653-1703	12	LF	THERMOPLASTIC SOLID TRAFFIC STRIPE, 24IN, WHITE (STOP BARS)		
653-6006	60	SY	THERMOPLASTIC TRAF STRIPING, 8" SOLID WHITE HATCH, 5' O.C.		
900-0526	2	EA	FIXED STEEL BOLLARDS		
900-0527	4	EA	REMOVABLE STEEL BOLLARDS		
900-0039	65	SF	FIRED CLAY BRICK PAVERS BANDING, PER CITY OF NEWNAN DOWNTOWN STANDARDS		

900-0039	180	SF	FIRED CLAY BRICK ADA PAVERS RAMPS, MATCH EXISTING		
900-0528	2	EA	BENCH		
900-0529	2	EA	TRASH RECEPTACLE		
900-0529	2	EA	RECYCLING RECEPTACLE		
900-0530	0	EA	BIKE RACK, LINC CUSTOM BRANDING		
900-0531	2	EA	PET WASTE STATION		

Newnan Linc A- Section A Sub Total

NEWMAN LINC DOWNTOWN CONNECTOR: PHASE A - Section B: Bridges / Retaining Walls

Item Number	Quantity	Units	Item Description	Unit Price	Cost
-------------	----------	-------	------------------	------------	------

WALL 1: CAST-IN-PLACE, STONE VENEER AND CAP (E WASHINGTON, STA 4+77 TO 6+20)

500-3101	50	CY	CLASS A CONCRETE, RETAINING WALL (INCL REINF)		
607-3000	900	SF	GRANITE STONE VENEER, 2 IN, PER DETAILS		
607-3000	150	LF	GRANITE STONE RUBBLE CAP, 4 IN, PER DETAILS		
515-1000	160	LF	METAL HANDRAIL, SPCL DESIGN (POST & CABLE, PER DETAILS SHEET 32-000A)		

WALL 2: MODULAR BLOCK RETAINING WALL SYSTEM (FIELD ST, STA 9+72 TO 10+82)

630-0000	1	LS	COMPLETE: MODULAR BLOCK RETAINING WALL SYSTEM (FIELD ST, STA 10+16 TO 9+66), CONTRACTOR DESIGN, MAX 6' HT		
----------	---	----	-----------------------------------------------------------------------------------------------------------	--	--

WALL 3: CAST IN PLACE, TURNDOWN EDGE WALL (STA 15+44 TO 17+46)

500-3101	32	CY	CLASS A CONCRETE, RETAINING WALL, ASHLAR FINISH (INCL REINF)		
500-3101	10	CY	STRUCTURAL SLAB SPAN & FOOTINGS		
515-1000	206	LF	METAL HANDRAIL, SPCL DESIGN (POST & CABLE, PER DETAILS SHEET 32-000A)		

TOP DOWN BOARDWALK STRUCTURE (STA 18+09 TO 23+70)

500-3101	13	CY	CLASS A CONCRETE, BOARDWALK ABUTMENT & WING WALLS, ASHLAR FINISH (INCL REINF) (STA 18+09 & 23+70)		
502-1000	561	LF	TOP DOWN BOARDWALK STRUCTURE WITH HANDRAILS (STA 1+59.91 to STA 8+87.26), PER DETAILS		
502-9000	75	LF	TIMBER HANDRAILS AT BOARDWALK APPROACH, PER DETAILS		
502-1500	1	LS	GLULAM BEAM TREATED TIMBER BRIDGE SPAN (35 LF, STA 23+35 TO 23+70)		

STRUCTURAL SLAB: CAST IN PLACE (STA 17+15)

500-3101	13	CY	CLASS A CONCRETE, STRUCTURAL SLAB AND ABUTMENTS (INCL REINF)		
515-1000	40	LF	METAL HANDRAIL, SPCL DESIGN (POST & CABLE, PER DETAILS SHEET 32-000A)		
207-2023	5	CY	FOUND BK FILL MATL, TPII (#57 STONE)		
603-7000	40	SY	PLASTIC FILTER FABRIC		

Newnan Linc A- Section B Sub Total

NEWMAN LINC DOWNTOWN CONNECTOR: PHASE A - Section C: Erosion Control / Storm Drainage

Item Number	Quantity	Units	Item Description	Unit Price	Cost
-------------	----------	-------	------------------	------------	------

163-0300	4	EA	CONSTRUCTION EXIT		
163-0301	1	LS	TEMPORARY REFUELING AREA		
163-0402	1	LS	TEMPORARY CONC. WASHDOWN		
163-0530	50	LF	CONSTRUCT & REMOVE 18" FILTER MEDIA SOCK CHECK DAMS		
163-0550	5	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE F		
163-0550	5	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE P		
163-0525	12	EA	CONSTRUCT, MAINTAIN, & REMOVE SEDIMENT BARRIER J-HOOKS		
165-0030	3000	LF	MAINTENANCE OF TEMPORARY SEDIMENT BARRIER, TYPE S		
165-0041	50	LF	MAINTENANCE OF CHECK DAMS - ALL TYPES		
165-0101	4	EA	MAINTENANCE OF CONSTRUCTION EXIT		
165-0105	10	EA	MAINTENANCE OF INLET SEDIMENT TRAP		
167-1000	1	EA	WATER QUALITY MONITORING AND SAMPLING, AS SPECIFIED IN PLANS PER APPENDIX 1 REQUIREMENTS		

167-1500	12	MO	WATER QUALITY INSPECTIONS (DAILY, WEEKLY, MONTHLY, & RAINFALL EVENTS)		
603-2180	4	SY	RIVER ROCK (STONE SIZE 3-4 IN) (24X24X12)IN		
167-1500	1	EA	LARGE SIGN AS SPECIFIED IN PLANS PER APPENDIX 1 REQUIREMENTS		
550-1060	5	LF	STORM DRAIN PIPE, 6 IN, HDPE		
550-1240	20	LF	STORM DRAIN PIPE, 24 IN, HDPE, H 1-10		
550-1080	1	EA	8" INLINE DRAIN W/ DOMED GRATE		
668-0000	1	EA	YARD INLET W/ EJ 1045Z FRAME & 1040 O2 GRATE (OR APPROVED EQUAL)		
668-1100	1	EA	CATCH BASIN, GP 1 (1033D C.B. DOGHOUSE)		
668-5000	1	EA	JUNCTION BOX (DOGHOUSE)		
668-7024	1	EA	DRAIN INLET, 24 IN, INCL. ADA GRATE & FRAME & REMOVAL EXIST. C.B. TOP		
700-6910	2	AC	PERMANENT GRASSING (INCL. SOIL TESTS AS SPECIFIED IN PLANS PER APPENDIX 1 REQUIREMENTS)		
700-8000	2	AC	FERTILIZER MIX GRADE		
716-2000	1000	SY	EROSION CONTROL MATS, SLOPES		

Newnan Linc A- Section C Sub Total

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE A - Section D: Landscaping

Item Number	Quantity	Units	Item Description	Unit Price	Cost
700-9400	7	EA	OCTOBER GLORY RED MAPLE, 3 IN CAL.		
700-9400	4	EA	NATCHEZ CRAPE MYRTLE, 2.5 IN CAL.		
700-9400	18	EA	COMPACT JAPANESE HOLLY, 5 GAL.		
700-9400	1305	EA	BIG BLUE LILYTURF		
700-9400	201	EA	REBLOOMING DAYLILY		
700-9410	5300	SF	SOD "CONTRACTOR TO VERIFY & MATCH EXISTING GRASS TYPE"		
702-9025	38	EA	MULCH		

Newnan Linc A- Section D Sub Total

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE A -Section E: Utilities

Item Number	Quantity	Units	Item Description	Unit Price	Cost
611-8001	1	EA	ADJUST WATER VALVE BOX TO GRADE (STA 1+05), PER PLANS		
611-8003	1	EA	TEMPORARY BRACING, EXISTING POWER POLE (STA 5+30) FOR WALL CONSTRUCTION, PER PLANS		
611-8050	1	EA	ADJUST COMMUNICATIONS MANHOLE TO GRADE (STA 1+75), PER PLANS		
611-8051	1	EA	ADJUST SANITARY SEWER MANHOLE LID TO GRADE (STA 11+50), PER PLANS		
660-0000	1	LS	TIE TO EXISTING SEWER, INCL. ABANDONMENT/REMOVAL OF EXISTING LINES & REMOVAL OF EXISTING MANHOLE		
660-0806	60	LF	SANITARY SEWER PIPE, 6 IN, DUCTILE IRON		
660-0808	120	LF	SANITARY SEWER PIPE, 8 IN, DUCTILE IRON		
668-3300	3	EA	SANITARY SEWER MANHOLE, TP 1		

Newnan Linc A- Section E Sub Total

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE A TOTAL ESTIMATED CONSTRUCTION COST

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE B - BID FORM PROPOSAL

NEWNAN LINC DOWNTOWN CONNECTOR: PHASE B -Section A: Roadway / Trail

Item Number	Quantity	Units	Item Description	Unit Price	Cost
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE FOR TRAIL (INCLUDING DEMOLITION & TREE REMOVAL)		
444-1000	4,050	LF	SAWED JOINTS IN EXISTING PAVEMENTS -PCC		
441-6022	50	LF	CONC CURB & GUTTER, 6 IN X 30 IN & 24 IN TP2		
441-0105	5,410	SY	CLASS A CONCRETE TRAIL, 5 IN, 12 FT, (INCL ADA RAMPS & POCKET PARKS AT STA 9+25 & STA 23+75)		
636-1041	66	SF	LINC TRAIL SIGN MATL 0.125 ALUM, DIRECT PRINT, PER DETAILS		

681-3740	9	EA	REGULATORY SIGN SQUARE ALUMINUM POST, PER DETAILS		
681-3740	1	LS	KIOSK SIGN PER DETAILS (CJ HICKS PARK)		
681-3740	1	EA	MILE MARKER SIGN SQUARE ALUMINUM POST, PER DETAILS		
636-1033	80	SF	MUTCD HIGHWAY SIGNS		
636-3010	112	LF	MUTCD HIGHWAY SQUARE POST, 14 FT.		
222-1002	1,550	SY	#57 STONE (CLEAN), 6 IN, (ROOT BRIDGING AREAS)		
603-7000	1,550	SY	PLASTIC FILTER FABRIC (ROOT BRIDGING AREAS)		
643-8200	1,750	LF	BARRIER TREE FENCE (ORANGE), 4 FT (ROOT BRIDGING AREAS)		
652-5302	108	LF	TRAIL CROSSWALK STRIPE, 12 IN, GREEN CASTEK COLOR SAFE ANTI-SKID, PER DETAILS.		
652-6403	5,015	LF	PAINT SKIP TRAF STRIPE, 4 IN, GREEN (TRAIL CL) (INCL CJ HICKS PARK)		
900-0526	6	EA	FIXED STEEL BOLLARDS		
900-0527	3	EA	REMOVABLE STEEL BOLLARDS		
754-5000	4	EA	BENCH		
754-4000	2	EA	TRASH RECEPTACLE		
754-4000	2	EA	RECYCLING RECEPTACLE		
754-4000	2	EA	PET WASTE STATION		
999-3800	4	EA	RAPID FLASHING BEACON SYSTEM (AT FARMER ST & ROBERTS RD)		
Section A Sub Total					

NEWANAN LINC DOWNTOWN CONNECTOR: PHASE B - Section B: Bridges / Retaining Walls					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
207-2023	45	CY	FOUND BK FILL MATL, TPII (#57 STONE)		
500-3800	75	CY	STRUCTURAL SLABS (STA 10+65, 12+75, 14+15, 32+25, 33+65, 34+50 & TBD, PER DETAILS		
500-3800	46	CY	BRIDGE ABUTMENTS & WING WALLS W/ ASHLAR FINISH		
515-1000	95	LF	HANDRAIL - BREAKAWAY POST & RAILING (AT GREISON TRAIL BOX CULVERT APPROACH), PER DETAILS		
515-1000	390	LF	HANDRAIL - POST & CABLE (AT BRIDGE APPROACH, STRUCTURAL SLAB LOCATIONS, & GREISON TRAIL WING WALL), PER DETAILS		
520-2208	180	LF	PILE ENCASEMENT, 8IN STEEL PIPE PILE		
534-1000	1	LS	PREFAB PED STEEL BRIDGE COMPLETE, 12'X43' TRAILBLAZER		
603-7000	200	SY	PLASTIC FILTER FABRIC		
Section B Sub Total					

NEWANAN LINC DOWNTOWN CONNECTOR: PHASE B - Section C: Erosion Control / Storm Drainage					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
163-0300	5	EA	CONSTRUCTION EXIT		
163-0300	1	LS	TEMPORARY CONC. WASHDOWN ECO PAN		
163-0520	30	LF	CONSTRUCT AND REMOVE TEMPORARY PIPE, 18 IN HDPE		
163-0527	1	EA	CONSTRUCT & REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP		
163-0530	300	LF	CONSTRUCT & REMOVE 18" FILTER MEDIA SOCK CHECK DAMS		
163-0530	10	LF	CONSTRUCT, MAINTAIN, & REMOVE 18" FILTER MEDIA SOCK AT PIPE INLETS		
163-0529	10,900	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE S WITH MULCH BERM		
163-0550	1	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE F		
163-0550	9	EA	CONSTRUCT, MAINTAIN, & REMOVE SEDIMENT BARRIER J-HOOKS		
165-0030	2,800	LF	MAINTENANCE OF TEMPORARY SEDIMENT BARRIER, TYPE S		
165-0041	100	LF	MAINTENANCE OF CHECK DAMS - ALL TYPES		
165-0101	5	EA	MAINTENANCE OF CONSTRUCTION EXIT		
165-0105	1	EA	MAINTENANCE OF INLET SEDIMENT TRAP		
167-1000	2	EA	WATER QUALITY MONITORING AND SAMPLING, AS SPECIFIED IN PLANS PER APPENDIX 1 REQUIREMENTS		
167-1500	12	MO	WATER QUALITY INSPECTIONS (DAILY, WEEKLY, MONTHLY, & RAINFALL EVENTS)		
668-2100	1	EA	DROP INLET, GP 1 (WITH PEDESTAL TOP, PER DETAIL)		
550-1180	120	LF	STORM DRAIN PIPE, 18 IN, HDPE, H 1-10		

550-1240	40	LF	STORM DRAIN PIPE, 24 IN, HDPE, H 1-10		
550-4218	5	EA	FLARED END SECTION, 18 IN (PER DETAIL)		
550-4224	2	EA	FLARED END SECTION, 24 IN (PER DETAIL)		
603-1012	240	SY	STN PLAIN RIP RAP, 12 IN (RIVER ROCK 6"-8")		
603-2997	240	SY	FILTER BLANKET (FOR RIP RAP/RIVER ROCK)		
700-6910	2.25	AC	PERMANENT GRASSING (INCL. SOIL TESTS AS SPECIFIED IN PLANS PER APPENDIX 1 REQUIREMENTS)		
700-8000	2.25	AC	FERTILIZER MIX GRADE		
716-2000	4,700	SY	EROSION CONTROL MATS, SLOPES		
Section C Sub Total					

NEWMAN LINC DOWNTOWN CONNECTOR: PHASE B - Section D: Landscaping					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
700-9400	4	EA	CHEROKEE PRINCESS' FLOWERING DOGWOOD		
700-9400	132	EA	BIG BLUE LILYTURF		
700-9400	42	EA	REBLOOMING DAYLILY		
702-9025	15	EA	MULCH		
Section D Sub Total					

NEWMAN LINC DOWNTOWN CONNECTOR: PHASE B - Section E: Utilities					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
611-8002	4	EA	ADJUST SANITARY SEWER MANHOLE LID TO GRADE PER PLANS (STA: 0+83, 8+40, 14+95 & 29+30), PER PLANS		
Section E Sub Total					

NEWMAN LINC DOWNTOWN CONNECTOR: PHASE B TOTAL ESTIMATED CONSTRUCTION COST					
----------------------------------------------------------------------------------	--	--	--	--	--

NEWMAN LINC- GREISON TRAIL "EXHIBIT BOX CULVERT" - BID FORM PROPOSAL

Quantities by Columbia Engineering					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
150-1000	1	LS	TRAFFIC CONTROL		
163-0232	0.1	AC	TEMPORARY GRASSING		
163-0240	0.2	TN	MULCH		
163-0300	1	EA	CONSTRUCTION EXIT		
165-0030	150	LF	MAINTENANCE OF TEMP SILT FENCE		
165-0101	1	EA	MAINTENANCE OF CONSTRUCTION EXIT		
171-0030	150	LF	TEMPORARY SILT FENCE, TYPE C		
207-0203	250	CY	TYPE II FOUNDATION BACKFILL MATERIAL		
210-0100	1	LS	GRADING COMPLETE		
301-1101	40	TN	GRADED AGGREGATE BASE		
318-3000	15	TN	AGGREGATE SURFACE COURSE		
402-3113	8	TN	ASPH TOPPING COURSE -12.5 MM		
402-3121	15	TN	ASPH BASE COURSE -12.5 MM		
402-3190	8	TN	ASPH BINDER COURSE -12.5 MM		
413-1000	30	GL	BITUM TACK COAT		
457-1010	90	SY	GEOGRID REINFORCEMENT, TP B		
500-3101	360	CY	CLASS A CONCRETE		
511-1000	43000	LB	BAR REINF STEEL		
636-1020	430	SF	HIGHWAY SIGNS, TYPE 1, MATL, REFL SHEETING, TYPE 3		
636-2070	810	LF	GALVINIZED STEEL POSTS, TYPE 7		
653-1501	70	LF	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE		
653-1502	70	LF	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, YELLOW		
654-1001	1	EA	RAISED PAVEMENT MARKERS TP 1		
700-6910	0.1	AC	PERMANENT GRASS		
700-7000	19	TN	AGRICULTURAL LIME		
700-8000	0.1	TN	FERTILIZER MIXED GRADE		
700-8100	6	LB	FERTILIZER NITROGEN CONTENT		
700-9300	50	SY	SOD		

Water Distribution and Sanitary Sewer					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
670-2390	125	LF	REMOVE WATER MAIN, 20 IN		
670-9280	55	LF	28" STEEL CASING		
670-1220	150	LF	WATER MAIN, 20 IN		
670-1490	2	EA	CUT AND CAP EXISTING WATER MAIN		
670-2002	2	EA	VALVE MARKER		

670-4490	4	EA	CONCRETE THRUST COLLAR		
Additional Cost					
441-0600	50	CY	CONC HEADWALLS		
550-1720	20	LF	STORM DRAIN PIPE, 72" RCP		
641-1200	71	LF	GUARDRAIL, TYPE W		
641-5001	1	EA	GUARDRAIL, TYPE W		
641-5012	1	EA	GUARDRAIL ANCHORAGE, TYPE 12		
NEWNAN LINC - GREISON TRAIL "EXHIBIT BOX CULVERT" TOTAL ESTIMATED CONSTRUCTION COST					

ALL PHASES: Allowances					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
999-1003		ALLOW	EROSION CONTROL NPDES PERMITS	\$5,000.00	\$5,000.00
				ALL PHASES: Allowances	

				Newnan Linc - Phase A- Total Cost	
				Newnan Linc - Phase B- Total Cost	
				Newnan Linc - GREISON TRAIL "EXHIBIT BOX CULVERT"- Total Cost	
				ALL PHASES: Allowances	
				\$5,000.00	
				TOTAL ESTIMATED CONSTRUCTION COST	