

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING JANUARY 28, 2021**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated January 8, 2021

**YORK COUNTY – SR 1037(ACC) #112809**

**PROPOSAL:\$20.28 PLANS:\$6.16 12X18:\$7.56 24X36:\$109.20 X-SEC:\$9.02 12X18:\$11.07 24X36:\$159.90**

This project includes repairing the roadway of Accomac Road and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 1037, SECTION ACC, in YORK COUNTY, HELLAM TOWNSHIP, from just north of Dark Hollow Road at Segment 0060 Offset 1915 to River Drive at Segment 0060 Offset 3238, for an overall project length of 1,218.00 linear feet (0.231 mile).

---

**MONROE COUNTY – SR 4002(0) #114328**

**PROPOSAL:\$15.00 PLANS 8.5X11:\$3.36**

This project is the application of an epoxy high friction surface treatment with bauxite aggregate to many crash identified locations within District 5-0. Lead project MPMS #114328 (NEPA), 114343 (LVTS) and 114388 (RATS) for a district-wide contract. Approximate project length 11,220 feet (2.13 miles).

---

**ERIE COUNTY – SR 0000(---) #115803**

**PROPOSAL:\$15.84**

For maintenance and repair of existing highway lighting systems, existing rectangular rapid flashing device system, and Type A signs, as indicated on the approved drawings included in the bid package for STATE ROUTE 0000, SECTION --, in CRAWFORD, ERIE, MERCER, and VENANGO COUNTIES and various municipalities.

---

**VENANGO COUNTY – SR 0000(---) #115840**

**PROPOSAL:\$20.40**

For drilling, core boring, geotechnical investigations and other miscellaneous construction, as indicated on the bid package for District-wide drilling, in CRAWFORD, ERIE, FOREST, MERCER, VENANGO and WARREN COUNTIES, in various municipalities.

---

**CLINTON COUNTY – SR 477(A01) #3784**

**PROPOSAL:\$27.24 PLANS:\$21.56 12X18:\$26.46 24X36:\$382.20 X-SEC:\$3.96 12X18:\$4.86 24X36:\$70.20**

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAY in CLINTON COUNTY, LOGANTON BOROUGH, Commonwealth of Pennsylvania, STATE ROUTE 0477 SECTION A01. The project is situated as follows: On State Route 0477 from Segment 0300 Offset 2484 to Segment 0300 Offset 1709. The total construction length is approximately 575 feet (0.11 miles). For the removal of the existing structure and construction of its replacement, a Single-Span Comp. P/S Concrete Spread Box Beam Bridge. Construction includes Superpave Asphalt Mixture Designs for the base, binder, and wearing courses, piping, inlet, guide rail, pavement markings, and miscellaneous construction as indicated on the approved drawings included in the bid package. Work also includes structural repairs to miscellaneous structures in Clinton, Juniata, and Mifflin Counties.

---

**POTTER COUNTY – SR 4009(A01) #4913**

**PROPOSAL:\$10.56 PLANS:\$4.62 12X18:\$5.67 24X36:\$81.90 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30**

The description and location of the project is as follows: This work is the furnishing and placement of a 9.0' x 6'-6" precast reinforced concrete box culvert and inlet and outlet sections over Baker Creek at a Department prepared site, construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base, binder and wearing courses and furnishing and placement of guide rail, and miscellaneous construction all within a length of approximately 450 linear feet (0.085 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 4009 SECTION A01, in POTTER COUNTY, HEBRON TOWNSHIP. On SR 4009 from Segment 0030/Offset 1865 to Segment 0040/Offset 0294.

---

**FOREST COUNTY – SR 62(311) #84316**

**PROPOSAL:\$9.96 PLANS 8.5X11:\$3.72**

For milling, paving, drainage, tree trimming/removal, guide rail, pavement markings, and delineation as indicated on the approved drawings included in the bid package for STATE ROUTE 62 SECTION 311, in Forest COUNTY Hickory TOWNSHIP from approximately segment 230 offset 0120' to segment 290 offset 1000'.

---

**BUTLER COUNTY – SR 19(29C) #104233**

**PROPOSAL:\$11.28 PLANS:\$22.66 12X18:\$27.81 24X36:\$401.70 X-SEC:\$14.30 12X18:\$17.55  
24X36:\$235.50**

Intersection Improvements, roadway improvements and signal installation along US 19, Little Creek Road, Mercer Road, and Wise Road and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 19, SECTION 29C, in Butler COUNTY Jackson TOWNSHIP from approximately 0.6 miles north of Zelenople Borough at segment 230 offset 1239 to approximately 0.1 miles south of Lancaster Township line at segment 250 offset 0052.

---

**JEFFERSON COUNTY – SR 3039(553) #107616**

**PROPOSAL:\$12.60 PLANS:\$7.70 12X18:\$9.54 24X36:\$136.50 X-SEC:\$2.20 12X18:\$2.70 24X36:\$39.00**

This project consists of replacing the existing structure carrying SR 3039 (Five Mile Run Road) over a tributary to Five Mile Run and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 3039, SECTION 553, in Jefferson COUNTY, Knox TOWNSHIP from approximately 0.4 miles north of Ramsaytown at segment 0010 offset 2005 to approximately 0.5 miles south of Colon at segment 0010 offset 2486.

---

**CLARION COUNTY – SR 322(354) #114550**

**PROPOSAL:\$13.56 PLANS:\$3.74 12X18:\$4.59 24X36:\$66.30**

Preservation of the existing structure carrying US 322 over the Clarion River to include minor deck repair and latex deck overlay and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 322, SECTION 354, in Clarion COUNTY Clarion TOWNSHIP from approximately 1.3 miles NW of Clarion at segment 306 offset 604 to approximately 1.5 miles NW of Clarion at segment 320 offset 066.

---

**ERIE COUNTY – SR 5(202) #99765**

**PROPOSAL:\$12.00 PLANS 8.5x11:\$5.28**

For milling and resurfacing using Superpave Asphalt Mixtures, as well as guiderail, drainage, ADA Curb Ramps, pavement markings and delineation, as indicated on the approved drawings included in the bid package for STATE ROUTE 5 in Erie COUNTY Lawrence Park TOWNSHIP from approximately segment 710 offset 0 to approximately segment 920 offset 2076.

---

**DAUPHIN COUNTY – SR 0000(---) #115552**

**PROPOSAL:\$10.80**

This project is for the installation and maintenance of major guide signs along various routes in District 8-0 and other miscellaneous construction, all as indicated in the Bid Package for VARIOUS STATE ROUTES, VARIOUS SECTIONS, in Adams, Cumberland, Dauphin, Franklin, Lancaster, Lebanon, Perry, & York Counties.

---

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**ECMS ADVANCED INFORMATION – LETTING JANUARY 28, 2021**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**LUZERNE COUNTY – SR 424(390) #70467** – *Moved from 12/10/20 to 1/14/20 to 1/21/20*

**PROPOSAL:\$192.72 PLANS:\$76.56 12X18:\$93.96 24X36:\$1,357.20 X-SEC:\$41.80 12X18:\$51.30 24X36:\$741.00 Ex St:\$9.02 12x18:\$11.07 24x36:\$159.90**

The SR 0424, Section 390 project involves an extension of SR 0424, commonly referred to as the Hazleton Beltway, from the I-81/Exit 141 Interchange to Humboldt Industrial Park (HIP) in Hazle Township, Luzerne County. The approximately 1.1-mile long extension will involve the construction of a four-lane roadway from the current termination of the beltway just west of I-81 to Commerce Drive. The roadway will require an at-grade railroad crossing and provide access to the White Birch Road extension directly south of the railroad. Traffic will proceed onto Commerce Drive, Forest Road, and this newly-constructed White Birch Road, a two-lane road to Maplewood Drive, which connects to SR 0924. Turning lanes will be added to the intersections of SR 0424 and I-81 northbound ramps, SR 0424 and I-81 southbound ramps, SR 0424 and Commerce Drive, and Commerce Drive and Forest Road. This extension will ultimately connect the Hazleton Beltway to SR 0924 west of I-81, utilizing HIP's existing roadway network. There are two existing bridges over I-81 within the project limits, SR 0424 at Interchange 141. The existing bridges are 60' wide and striped for three (3) lanes. To facilitate five (5) lanes, the existing bridge cross slopes will be modified to move the profile grade point and the lanes restriped. This will be done with a latex modified concrete overlay (LMCO) of the existing bridge decks. The proposed typical section will result in five (5) 11'-0" lanes with two (2) 2'-6" shoulders. Modifications to the bridge approach slab will also be necessary. The existing approach slab width is designed to match the current travel lane width on the bridges. With the addition of lanes, the proposed roadway will require wider approach slabs. Approach shoulders will also be modified to concrete and flared to match the radius of the intersection. Three bioretention basins will be used to control stormwater volume throughout the project. The overall project length of 1.771 miles (9,350 linear feet) plus Ramps and Township Roads as indicated on the approved drawings included in the bid package.

---

**NORTHUMBERLAND COUNTY – SR 180(117) #97549** – *Moved from 12/10/20 to 1/14/20 to 1/21/20*

**PROPOSAL:\$80.40 PLANS:\$55.00 12X18:\$67.50 24X36:\$975.00 X-SEC:\$11.88 12X18:\$14.58 24X36:\$210.60 Ex St:\$19.80 12x18:\$24.30 24x36:\$351.00**

The description and location of the project are as follows: For Resurfacing, Bridge Replacement and Bridge Preservation including excavation, selected borrow excavation, superpave asphalt mixture design base, binder, scratch, and wearing courses, stone matrix asphalt mixture design wearing course, subbase, milling, drainage, guide rail, right-of-way fence, rumble strips, precast cement concrete block slope wall, pavement markings, signs, epoxy coated steel WWF, reinforcement bars, removal of existing bridge, removal of portion of existing bridge, protective coating for reinforced concrete surfaces, concrete bridge deck repair, epoxy overlay, neoprene strip seal gland replacement, construction of a two span prestressed concrete PA bulb-tee beam bridge or an approved equal over State Route 180, mechanically stabilized abutment or wingwall or approved equal, self-consolidating cement concrete, repair deteriorated concrete jacket, temporary access road, jacking bridge superstructure, adhesive anchor, neoprene strip seal dam replacement, FRP repair of concrete surfaces, elastomer waterproofing membrane on bridge decks, repair deteriorated concrete, asphaltic plug expansion system, removal of existing piles, UV activated cured in place liner, and other related work within an overall length of 57,267 linear feet (10.84 miles) all as indicated on the approved drawings included in the bid package for STATE ROUTE 180, SECTION 117 from approximately 6.96 miles south of the intersection with State Route 405 at Segment 0540 Offset 2607 (Eastbound)/ Segment 0545 Offset 0850 (Westbound) and approximately 2.05 miles north of the intersection with State Route 254 at Segment 0594 Offset 2686 (Eastbound)/ Segment 0595 Offset 2707 (Westbound) in DELAWARE TOWNSHIP and TURBOT TOWNSHIP, NORTHUMBERLAND COUNTY and STATE ROUTE 254, SECTION 057 from approximately 1.05 miles east of the intersection with State Route 405 at Segment 0060 Offset 0069 and approximately 2.11 miles west of the intersection with State Route 80 at Segment 0060 Offset 0575 in TURBOT TOWNSHIP, NORTHUMBERLAND COUNTY.

**GREENE COUNTY – SR 0000(SWM) #114211 – Moved from 12/10/20 to 1/14/20 to 1/21/20**

**PROPOSAL:\$97.92 PLANS:\$10.56 12X18:\$12.96 24X36:\$187.20** This project consists of restoring existing Storm Water Facilities back to their natural state. This includes excavation, new rock lined channels, cleaning existing ditches & pipe culverts, tree removal, mowing, seeding & mulching, repairing and replacing Right-of-Way fence and other miscellaneous work to be completed at each Storm Water location. Work will be done in Fayette, Greene, Washington and Westmoreland Counties.

---

**ELK COUNTY – SR 555(P23) #4354**

**PROPOSAL:\$25.08 PLANS:\$12.98 12X18:\$15.93 24X36:\$230.10 X-SEC:\$4.40 12X18:\$5.40 24X36:\$78.00**

The description and location of the project is as follows: For the improvement of a certain section of STATE HIGHWAY in ELK COUNTY, BENEZETTE TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 0555, SECTION P23. The project being situated as follows: On State Route 0555 from Segment 0380/Offset 0397 to Segment 0370/Offset 2721 in Elk County over Dents Run. For rehabilitation work of the structure including bridge superstructure replacement, and repointing of abutment stone. Roadway includes Superpave Asphalt Mixture Designs for the base, binder, and wearing courses, pavement base drain, guide rail, pavement markings, and miscellaneous construction for a total construction length of approximately 800 linear feet (0.152 miles) as indicated on the approved drawings included in the bid package.

---

**McKEAN COUNTY – SR 346(A11) #81411**

**PROPOSAL:\$14.88 PLANS:\$4.84 12X18:\$5.94 24X36:\$85.80 X-SEC:\$0.88 12X18:\$1.08 24X36:\$15.60**

The description and location of the project is as follows: This work is the furnishing and placement of an 9.0' x 5.5' precast reinforced concrete box culvert and inlet and outlet sections over Unnamed trib. to Knapp Creek at a Department prepared site, construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base, binder, and wearing courses and furnishing and placement of guide rail, and miscellaneous construction all within a length of approximately 225 linear feet (0.043 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 0346 SECTION A11, in MCKEAN COUNTY, OTTO TOWNSHIP. On SR 0346 (Main Street), from Segment 0550 Offset 2123 to Segment 0550 Offset 1798 Station 519+75 to Station 523+00. North-west of town of Prentisvale.

---

**CENTRE COUNTY – SR 1006(A01) #91416**

**PROPOSAL:\$15.12 PLANS:\$8.80 12X18:\$10.80 24X36:\$156.00 X-SEC:\$5.50 12X18:\$6.75 24X36:\$97.50**

The description and location of the project is as follows: This work is the furnishing and placement of an 15.0' x 6.0' precast reinforced concrete box culvert and inlet and outlet sections over Unnamed trib. to Bald Eagle Creek at a Department prepared site, construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base, binder, and wearing courses, installation of temporary roadway, furnishing and placement of guide rail, and miscellaneous construction all within a length of approximately 850 linear feet (0.161 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 1002 SECTION A15, in CENTRE COUNTY, BOGGS TOWNSHIP. On SR 1006 (Water Street), from Segment 0030 Offset 0744 to Segment 0030 Offset 1694 Station 1983+50 to Station 1993+00 which is located north-west of Milesburg.

---

**CLEARFIELD COUNTY – SR 3016(A03) #91509**

**PROPOSAL:\$14.88 PLANS:\$5.50 12X18:\$6.75 24X36:\$97.50 X-SEC:\$1.76 12X18:\$2.16 24X36:\$31.20**

The description and location of the project is as follows: This work is the furnishing and placement of a 15'-0" x 5'-6" precast reinforced concrete box culvert and inlet and outlet sections over Campbell Run at a Department prepared site, construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base, binder and wearing courses and furnishing and placement of guide rail and miscellaneous construction all within the length of approximately 405.75 linear feet (0.077 miles), as indicated on the approved drawings included in the bid package for STATE ROUTE 3016, SECTION A03, in CLEARFIELD COUNTY, FERGUSON TOWNSHIP.

---

**JUNIATA COUNTY – SR 3010(A01) #112076**

**PROPOSAL:\$15.96 PLANS:\$4.62 12X18:\$5.67 24X36:\$81.90 X-SEC:\$2.64 12X18:\$3.24 24X36:\$46.80**

The description and location of the project is as follows: This work is the furnishing and placement of an 11.0' x 7.5' precast reinforced concrete box culvert and inlet and outlet sections over Tribute to Tuscarora Creek at a Department prepared site, construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base and wearing courses and furnishing and placement of guide rail, and miscellaneous construction all within a length of approximately 435 linear feet (0.082 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 0346 SECTION A11, in JUNIATA COUNTY, MILFORD TOWNSHIP. On SR 3010 (Lions Club Park Road) from Segment 0020 Offset 0316 to Segment 0020 Offset 0866 Station 40+00 to Station 45+50. South-west of Port Royal Borough.

---

**CENTRE COUNTY – SR 26(EPX) #114197**

**PROPOSAL:\$15.72 PLANS:\$6.16 12X18:\$7.56 24X36:\$109.20**

The description and location of the project is as follows: For the improvement of a certain section of STATE HIGHWAY in CENTRE, ELK, McKEAN, POTTER, CLINTON, AND JUNIATA COUNTIES, VARIOUS TOWNSHIPS AND BOROUGH, Commonwealth of Pennsylvania, STATE ROUTE 0026, SECTION EPX. This work is the improvement of various bridges including applications of epoxy based surface treatments, and other miscellaneous construction, as indicated on the approved drawings included in the bid package. Approximate project length 1146ft (.8 miles).

---

**ALLEGHENY COUNTY – SR 7301(LOC) #114243**

**PROPOSAL:\$35.64**

The description and location of the project is as follows: For the maintenance and monitoring of the previously installed cable and vault dehumidification systems over a three year duration, all within a length of 3,534.26 Linear Feet (0.669 Miles) as indicated on the approved Attachments included in the Bid Package for SOUTH TENTH STREET BRIDGE DEHUMIDIFICATION SYSTEM PROJECT (Also known as the PHILIP MURRAY BRIDGE) in ALLEGHENY COUNTY, CITY OF PITTSBURGH, from the intersection with SR 837 (East Carson Street) at Station 100+00.00 to the intersection with Forbes Avenue (City Street) at Station 35+50.00.

---

**DELAWARE COUNTY – SR 0000(GRD) #115081**

**PROPOSAL:\$25.32**

This project is for the repair and/or replacement of guiderail, median barrier and/or their hardware, and Right-of-Way fence on various State Routes in Delaware County, Pennsylvania.

---

**DAUPHIN COUNTY – SR 0000(---) #115549**

**PROPOSAL:\$10.08 PLANS:\$4.18 12X18:\$5.13 24X36:\$74.10**

For the furnishing and application of white and yellow waterborne pavement markings along various state highways within Engineering District 8-0, various municipalities, Commonwealth of Pennsylvania, all within an overall project length of 5,716,539.00 linear feet (1,082.68 miles) as indicated on the approved drawings included in the Bid Package.

---

**WESTMORELAND COUNTY – SR 136(0) #115568**

**PROPOSAL:\$18.72 PLANS:\$5.50 12X18:\$6.75 24X36:\$97.50 Ex St:\$89.98 12x18:\$110.43 24x36:\$1,595.10**

The scope is bridge preservation activities 3/8" epoxy based surface treatment, minor type 2 deck repairs, replace neoprene compression and strip seals, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0136, SECTION 04M, in WESTMROELAND COUNTY SEWICKLEY TOWNSHIP over Various segments on twelve routes with 18 structures.

---

**CAMBRIA COUNTY – SR 3055(028) #94478**

**PROPOSAL:\$15.96 PLANS:\$4.62 12X18:\$5.67 24X36:\$81.90**

This project is for the preservation of Franklin Street Bridge carrying SR 3055 over Stoneycreek River in Cambria County. Preservation work includes the removal of the existing paint, repainting the structure, fabricated structural steel repair, replacement of the neoprene strip seal glands and deteriorated rivets and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 3055, SECTION 02B in CAMBRIA COUNTY, CITY OF JOHNSTOWN.

---

**HUNTINGDON COUNTY – SR 22(01M) #105978**

**PROPOSAL:\$39.84 PLANS:\$17.82 12X18:\$21.87 24X36:\$315.90 X-SEC:\$5.72 12X18:\$7.02 24X36:\$101.40**

This project is for the pavement preservation of approximately 9.8 miles of SR 0022 in Huntingdon County. Work includes milling and resurfacing, drainage improvements, guide rail upgrades, signing, traffic signal upgrades and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0022, SECTION 01M, in HUNTINGDON COUNTY, SMITHFIELD, HENDERSON & BRADY TOWNSHIPS, MILL CREEK BOROUGH at the locations indicated on the plans in the bid package.

---

**BUTLER COUNTY – SR 19(213) #109627**

**PROPOSAL:\$15.60 PLANS:\$10.34 12X18:\$12.69 24X36:\$183.30**

This project includes the resurfacing a portion of SR 0019 and also the milling of the existing bituminous wearing courses, bituminous patching, paving, leveling, binder and wearing courses, and minor drainage and guide rail upgrades and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0019, SECTION 213, in Allegheny COUNTY Marshall TOWNSHIP and Butler COUNTY Cranberry/Jackson/Lancaster TOWNSHIPS and Zelienople BOROUGH from approximately 0.1 miles north of the intersection of SR 0019 and Freedom Road at segment 0680 offset 3202/segment 0681 offset 3266 to approximately 1.8 miles south of Middle Lancaster at segment 0250 offset 0250.

---

**BEDFORD COUNTY – SR 4009(021) #110279**

**PROPOSAL:\$16.56 PLANS:\$3.08 12X18:\$3.78 24X36:\$54.60**

This project is for the pavement preservation of approximately 2.43 miles of SR 4009 in Bedford County. Work includes milling and resurfacing, guiderail, drainage, pavement markings, signing upgrades and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 4009, SECTION 021, in BEDFORD COUNTY, BEDFORD TOWNSHIP, BEDFORD BOROUGH at the locations indicated in the bid package.

---

**CHESTER COUNTY – SR 2014(PPA) #110776**

**PROPOSAL:\$25.20 PLANS:\$11.22 12X18:\$13.77 24X36:\$198.90**

This project is for construction of a 10 foot wide shared use path with cement concrete curb ramps, stormwater management facilities and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 2014, SECTION PPA, in CHESTER COUNTY EAST GOSHEN & WEST GOSHEN TOWNSHIPS from approximately Sta. 89+00.00 at segment 0040 offset 1779 to approximately Sta. 98+50.00 segment 0040 offset 2729.

---

**BUCKS COUNTY – SR 0000(APS) #111471**

**PROPOSAL:\$24.84 PLANS:\$9.90 12X18:\$12.15 24X36:\$175.50 X-SEC:\$5.72 12X18:\$7.02 24X36:\$101.40**

Construction of a 10-foot to 12-foot wide shared use path paralleling SR 0202 (Lower York Road) and includes the installation of a parking lot and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0000, SECTION APS, in BUCKS COUNTY, SOLEBURY TOWNSHIP from approximately Sta. 9+50 at the Judy House driveway to approximately Sta. 24+00 at the gravel driveway.

---

**CENTRE COUNTY – SR 1002(A15) #112738**

**PROPOSAL:\$15.00 PLANS:\$4.84 12X18:\$5.94 24X36:\$85.80 X-SEC:\$1.10 12X18:\$1.35 24X36:\$19.50**

The description and location of the project is as follows: This work is the furnishing and placement of an 6.5' x 3.5' precast reinforced concrete box culvert and inlet and outlet sections over Unnamed trib. to Marsh Creek at a Department prepared site, construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base, binder, and wearing courses and furnishing and placement of guide rail, and miscellaneous construction all within a length of approximately 235 linear feet (0.045 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 1002 SECTION A15, in CENTRE COUNTY, CURTIN TOWNSHIP. On SR 1002 (Marsh Creek Road), from Segment 0200 Offset 0558 to Segment 0200 Offset 0893 Station 868+40 to Station 871+75 which is located north-west of Howard.

---

**JEFFERSON COUNTY – SR 322(503) #114715**

**PROPOSAL:\$12.00 PLANS:\$4.18 12X18:\$5.13 24X36:\$74.10**

This project includes the resurfacing of a portion of SR 322 to include milling of the existing bituminous wearing surface, bituminous patching, pavement relief joints, paving, leveling, binder and wearing courses, and drainage and guide rail updates and other miscellaneous construction, as indicated on the approved drawings included in the bid package for State Route 322, Section 503, in Clarion County, Clarion & Limestone Townships AND Jefferson County, Corsica & Brookville Boroughs and Union & Rose Townships from approximately .8 miles east of SR 2005 at segment 0560 offset 2331 to approximately .2 miles east of the Brookville Borough line at segment 0150 offset 0055.

---

**ADAMS COUNTY – SR 0000(---) #115550**

**PROPOSAL:\$10.08 PLANS:\$3.08 12X18:\$3.78 24X36:\$54.60**

For the placement/replacement of raised pavement markers (RPMs) and/or pavement marker reflectors along various state highways in ADAMS, YORK, LANCASTER, and PERRY COUNTIES, Commonwealth of Pennsylvania, within an overall length of 1,523,392.00 linear feet (288.5 miles) as indicated on the approved drawings included in the Bid Package.

---

**BEDFORD COUNTY – SR 0000(---) #115776**

**PROPOSAL:\$12.24 PLANS:\$6.60 12X18:\$8.10 24X36:\$117.00**

Description This project is for the application of painted pavement markings at various locations on STATE HIGHWAYS in BEDFORD, BLAIR, CAMBRIA, FULTON, HUNTINGDON and SOMERSET COUNTIES, VARIOUS TOWNSHIPS AND MUNICIPALITIES, Commonwealth of Pennsylvania, all as indicated on the approved drawings included in the bid package.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**