Addendum

Iowa Department of Transportation Office of Contracts

Date of Letting: July 20, 2021 Date of Addendum: July 15, 2021

C.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
005	25-0803-219	BRIDGE REPLACEMENT - PPCB	DALLAS	IM-NHS-080-3(219)11003-25 IM-NHS-080-3(222)11203-25 IM-NHS-080-3(224)11203-25	20JUL005A03

Make the following changes to the PLAN for Project # IM-NHS-080-3(219)110--03-25:


Replace SHEET B.3 with the attached SHEET B.3.

LOCATION				DIMENSIONS					6" 2	Earth 2	
ROAD IDENTIFICATION	STATION TO STATION		PW	НМА	(SGW)	PCC PW T SGW		Area	Special Backfill	Shoulder Construction	
			Feet	Inches	Feet	Feet	Inches	Feet	Square Yard	Tons	Station
I 80 EB	673+00.00	682+75.00	8	12	4.5	8	9	3.75	866.7	273.0	9.75
I 80 EB	682+75.00	685+25.00	8-20	12	4.5	8-20	9	3.75	388.9	122.5	2.50
I 80 EB	685+25.00	692+41.33	20	12	4.5	20	9	3.75	1591.8	501.2	7.16
I 80 EB	692+41.33	706+00.00	8	12	4.5	8	9	3.75	1207.7	380.5	13.59
* I 80 EB	706+00.00	716+00.00	14	12	4.5	14	9	3.75	1555.6	490.0	10.00
* I 80 EB	735+00.00	739+00.00	14	12	4.5	14	9	3.75	622.2	196.0	4.00
* I 80 EB	753+50.00	763+50.00	14	12	4.5	14	9	3.75	1555.6	490.0	10.00

Quantity calculations based on vertical pavement edges and a Speccial Backfill unit weight (lb/cf) of 140.

Normal section shown may be modified appropriately in areas of superelevated curves or other locations specifically designated by the Engineer.


- 1 Possible HMA 1:1 slope
- 2 Not a bid item
- * Location modified appropriately as designated by the Engineer.



DETOUR PAVING

4315 Modified

D_Detou MODIFIED



- ① Granular Backfill.
- ② 4" subdrain at flowline elevation of culvert shall be extended into the culvert a distance of 2' plus the height of the culvert. Granular Backfill covers subdrain and extends an additional 2'. Subdrain and granular backfill are incidental to culvert abandonment, plug.
- 3 Ends of culvert shall be plugged sufficiently.
- 4 Removal of headwalls may be required.

DETAILS OF CULVERT ABANDONMENT (Circular structures less than 10' Dia.)

IM-NHS-080-3(219)110--03-25 DALLASCOUNTY SHEET NUMBER PROJECT NUMBER pw:\\projectwise.dot.int.lan:PWMain\Documents\Projects\2508002017\Design_(219)_Grade\CADD_Files\Sheet_Files\SHT_25080219_B01.dgn